



LEGEND : ELECTRICAL INSTALLATION		
SYMBOL	DESCRIPTION(S)	QTY
	1 X 22W LED CEILING RECESSED WALL WASHER C/W DALI BALLAST	85
	1 X 32W LED CEILING RECESSED WALL WASHER C/W DALI BALLAST	8
	2 X 14W RECESSED TYPE T5 FLUO. FTG. C/W MIRROR REFLECTOR & ALUMINIUM CROSS BLADE. (DIMMABLE ELECTRONIC BALLAST EXCEPT FOR STORE)	3
	1 X 28W RECESSED TYPE T5 FLUO. FTG. C/W MIRROR REFLECTOR & TRANSPARENT DIFFUSER (ELECTRONIC BALLAST)	1
	1 X 28W T5 WALL MOUNTED BARE CHANNEL FLUO. LIGHT FTG. C/W ELECTRONIC BALLAST.	1
	1 X 12V/6W LED WALL MOUNTED TYPE UP / DOWN LIGHTING FTG.	2
	LIGHTING POINT FOR ID PANEL TO SMART CONTROL AT CONTROL ROOM	4
	10A 1 GANG ONE WAY LIGHTING SWITCH AT 1450mm AFFL.	3
	13A SWITCH SOCKET OUTLET AT 300mm AFFL.	62
	13A SWITCH SOCKET OUTLET AT ABOVE CEILING LEVEL FOR PROJECTOR	2
	13A SWITCH SOCKET OUTLET MOUNTED INSIDE FLOOR SERVICE BOX/JUNCTION BOX.	4
	13A SWITCH SOCKET OUTLET AT ABOVE CEILING LEVEL FOR WIFI SYSTEM	2
	13A SWITCH SOCKET OUTLET AT CEILING LEVEL FOR SPEAKER & SUBWOOFER	-
	13A SWITCH SOCKET OUTLET AT BELOW CEILING LEVEL FOR CCTV	2
	20A 1 GANG ONE WAY DOUBLE POLE SWITCH (FOR AIR CONDITIONING)	1
	8 GANG SMART SWITCH AT 1450mm AFFL.	2
	DIMMER SWITCH	1
	DISTRIBUTION BOARD AT 2100mm AFFL. (METAL CLAD, WALL MOUNTED TYPE)	1
	32A SINGLE PHASE POWER SUPPLY	1
	LIGHTING AUTOMATION PANEL	1
	30A SPN ISOLATOR POINT	1
	-50mm X 50mm TRUNKING @ CEILING FOR AUDIO AND VISUAL (BY ELECTRICAL CONTRACTOR)	AS SHOWN
	-25MM UPVC CONDUIT @ CEILING FOR AUDIO AND VISUAL (BY ELECTRICAL CONTRACTOR)	AS SHOWN
	-25MM UPVC CONDUIT @ FLOOR FOR AUDIO AND VISUAL C/W INSPECTION BOX (BY ELECTRICAL CONTRACTOR)	AS SHOWN
	-25MM UPVC CONDUIT @ WALL FOR AUDIO AND VISUAL (BY ELECTRICAL CONTRACTOR)	AS SHOWN
	UNDER FLOOR JUNCTION BOX (150mm X 150mm) FOR POWER, TELEPHONE & DATA CAST IN FLOOR SLAB. - DATA - 50mm X 25mm X 3.2mm UNDERFLOOR UPVC TRUNKING/CONDUIT. (CAST IN FLOOR SLAB) - POWER - 50mm X 25mm X 3.2 mm UNDERFLOOR UPVC TRUNKING/CONDUIT. (CAST IN FLOOR SLAB) - TELEPHONE - 50mm X 25mm X 2.5 mm UNDERFLOOR UPVC TRUNKING/CONDUIT. (CAST IN FLOOR SLAB)	AS SHOWN

LEGEND : TELEPHONE INSTALLATION		
SYMBOL	DESCRIPTION(S)	QTY
	COMPUTER/DATA (1G) UTP PT. C/W SOCKET OUTLET USING CAT. 6 CABLE IN UPVC CONDUIT/CONCEALED	8
	WIFI POINT C/W SOCKET OUTLET AT CEILING LEVEL USING CAT 6 CABLE IN UPVC CONDUIT/CONCEALED.	2
	DOMA CAMERA	2

NOTES:

- ALL M&E SERVICES WILL BE UNDER ELECTRICAL CONTRACTOR TO BE COORDINATED WITH ID CONTRACTOR FOR ALL FITMENT THAT REQUIRED CUTTING
- ALL DIMENSIONS TO BE VERIFIED AT SITE
- REFER TO APPROVED MATERIALS / FINISHES
- ALL EXISTING SITE CONDITION TO BE INSPECTED AND HIGHLIGHTED TO DESIGNER AND SITE MANAGER FOR VERIFICATION PRIOR TO ANY FABRICATION OF SHOP DRAWINGS.



ARCHITECTURE GROUP-STUDIO A
CPG CONSULTANTS PTE LTD
1 GATEWAY DRIVE #25-01
WESTGATE TOWER, SINGAPORE 608531
TEL: 6357 4888 FAX: 6357 4188

©2014, CPG Consultants Pte Ltd reserves all rights to these drawings, designs and/or any other data contained herein. No part of the said drawings, designs and/or other data may be reproduced, modified, transmitted or used in any form or by any means for any purpose without the prior written consent of CPG Consultants Pte Ltd other than the sole purpose for which such drawings, designs and/or other data are provided to licensed users on such terms as CPG Consultants Pte Ltd may prescribe.

Job Title
INTERIOR DESIGN WORKS FOR PROPOSED KDU PENANG
@ BATU KAWAN, PENANG MALAYSIA

Drawing Title
LECTURE THEATRE 1 - BLOCK D 1ST - 2ND FLOOR
MECHANICAL & ELECTRICAL LAYOUT PLAN

Senior Vice President	TAN PHENG CHEE
Vice President	PATRICK TAN
Principal Architectural Associate	-
Architectural Associate	-
Principal Interior Designer	BETH SONCUYA

TENDER DRAWING					
Drawn By	TEAM		Date:	JULY 16	
Checked By	BETH		Date:	JULY 16	
Project Code :	Drawing No. :	REV.	Scale :	1:75	
P5679	ID-FT-D-304-07	-	CAD Ref.		